



## Catalog No. RMS312240CHLBRB

Description: MTR STACK 2-400A 3PH3PH RNGL LVB +BRKRS

UPC No 783164673661

Home > Modular Metering > ReliaMod > ReliaMod Meter Module

### Descriptors

|          |                       |
|----------|-----------------------|
| Category | ReliaMod Meter Module |
|----------|-----------------------|

### Specifications

|                                                       |                                                                      |
|-------------------------------------------------------|----------------------------------------------------------------------|
| Enclosure                                             | N3R Outdoor                                                          |
| Meter Equipment Group (MEG) Approved                  | Yes                                                                  |
| Socket Amperage                                       | 400 A                                                                |
| Main Phase Input                                      | 3-Phase                                                              |
| Socket Phase Output                                   | 3-Phase                                                              |
| Voltage                                               | 208Y/120V                                                            |
| Socket Type                                           | Ringless                                                             |
| No of Sockets                                         | 2                                                                    |
| Socket Factory Installed Jaw Configuration            | 7-Jaw                                                                |
| Socket Bypass                                         | Lever                                                                |
| Horizontal Bus Amperage                               | 1200 A                                                               |
| Tenant Neutral Lugs (Per each socket) AWG/kcmil Al/Cu | (2) 2/0-500                                                          |
| Tenant Ground Lugs (Per each socket) AWG/kcmil Al/Cu  | #6-300                                                               |
| Meter Module Tenant Breaker Provisions                | Two 400A XT5N TMA 65 KAIC Tenant Breakers Included Factory Installed |
| Additional Notes                                      | For tenant breaker load lugs, please refer to breaker specifications |
| Height (Inches)                                       | 70.3                                                                 |
| Depth (Inches)                                        | 10.8                                                                 |
| Width (Inches)                                        | 23.3                                                                 |
| Estimated Weight (lbs)                                | 270                                                                  |