



Catalog No. RMS312140CHLBR

Description: MTR STACK 1-400A 2X 3PH RNGL LVB 42-100K

UPC No 783164673678

Home > Modular Metering > ReliaMod > ReliaMod Meter Module

Descriptors

Category	ReliaMod Meter Module
----------	-----------------------

Specifications

Enclosure	N3R Outdoor
Meter Equipment Group (MEG) Approved	Yes
Socket Amperage	400 A
Main Phase Input	3-Phase
Socket Phase Output	3-Phase
Voltage	208Y/120V
Socket Type	Ringless
No of Sockets	1
Socket Factory Installed Jaw Configuration	7-Jaw
Socket Bypass	Lever
Horizontal Bus Amperage	1200 A
Tenant Neutral Lugs (Per each socket) AWG/kcmil Al/Cu	#6-300kcmil
Tenant Ground Lugs (Per each socket) AWG/kcmil Al/Cu	#14-2/0
Meter Module Tenant Breaker Provisions	Accepts two 42-100 KAIC XT3 or XT4 Tenant Breakers (200A Max Each)
Additional Notes	For tenant breaker load lugs, please refer to breaker specifications
Height (Inches)	54.7
Depth (Inches)	10.8
Width (Inches)	20.1
Estimated Weight (lbs)	195