

### Catalog No. RMS212222HRLR

Description: MTR STACK 2-225A 3PH-1PH RGLS 42-100K

UPC No 783164682762

Home > Modular Metering > ReliaMod > ReliaMod Meter Module



Representative Image

#### Descriptors

|          |                       |
|----------|-----------------------|
| Category | ReliaMod Meter Module |
|----------|-----------------------|

#### Specifications

|                                                       |                                                                      |
|-------------------------------------------------------|----------------------------------------------------------------------|
| Enclosure                                             | N3R Outdoor                                                          |
| Meter Equipment Group (MEG) Approved                  | Yes                                                                  |
| Socket Amperage                                       | 225 A                                                                |
| Main Phase Input                                      | 3-Phase                                                              |
| Socket Phase Output                                   | 1-Phase                                                              |
| Voltage                                               | 120/240V                                                             |
| Socket Type                                           | Ringless                                                             |
| No of Sockets                                         | 2                                                                    |
| Socket Factory Installed Jaw Configuration            | 5-Jaw                                                                |
| Socket Bypass                                         | None                                                                 |
| Horizontal Bus Amperage                               | 1200 A                                                               |
| Meter Module Tenant Breaker Provisions                | Only Accepts 42-100 KAIC XT3 & XT4 Tenant Breakers                   |
| Additional Notes                                      | For tenant breaker load lugs, please refer to breaker specifications |
| Height (Inches)                                       | 57.9                                                                 |
| Depth (Inches)                                        | 9.6                                                                  |
| Width (Inches)                                        | 18.4                                                                 |
| Estimated Weight (lbs)                                | 185                                                                  |
| Tenant Neutral Lugs (Per each socket) AWG/kcmil Al/Cu | #6-300                                                               |
| Tenant Ground Lugs (Per each socket) AWG/kcmil Al/Cu  | #14-2/0                                                              |