



Representative Image

# Catalog No. PAM3015W

**Description:** LD CTR MCB 150A 30/60 AL N1 WH PON UL

**UPC No** 783164693454

**Home > Load Centers > Load Centers**

ABB ReliaHome makes homes reliable, with ease. We designed our ReliaHome load centers to be installed as fast as possible - and reliable so your customers can leave a job with confidence. They work seamlessly with all our residential circuit breakers, optimizing your stock.

## Descriptors

|             |                    |
|-------------|--------------------|
| Category    | Load Centers       |
| GO Schedule | RT                 |
| Grouping    | Single Phase - USA |

## Specifications

|                                                      |                              |
|------------------------------------------------------|------------------------------|
| # Branch Circuit 250A                                | 30                           |
| 1" Space                                             | 30                           |
| 1/2" Space                                           | 0                            |
| Amperage                                             | 150 A                        |
| Circuit Breaker Style                                | Plug-On Neutral              |
| Door                                                 | Yes                          |
| Enclosure                                            | Indoor                       |
| Enclosure Type                                       | Indoor, Combination          |
| Factory Installed Ground Kit                         | No                           |
| Feed                                                 | Either                       |
| Input/Output Voltage                                 | 120/240V ac                  |
| Interrupt Rating                                     | 22kAIC                       |
| Interrupting Capacity Rating                         | 22kAIC                       |
| Load Center Type                                     | P-Series (PON)               |
| Meter Socket Options: 200 Amp Main Breaker Installed | No                           |
| Meter Socket Options: High Amp Mode                  | None                         |
| NEMA Rating                                          | NEMA 1                       |
| No of Circuits                                       | 60                           |
| Phase                                                | 1 Phase                      |
| Service & Voltage                                    | 1 Phase, 3 Wire, 120/240V ac |
| Wires                                                | 3 Wire                       |

## Classifications

|                |    |
|----------------|----|
| UL/CUL Listing | UL |
|----------------|----|

